A.D.D. CONTROL SYSTEM

COMPONENTS



WIRING DIAGRAM





COMPONENTS INSPECTION

1. INSPECT A.D.D. SOLENOIDS

(a) Measure the resistance of the solenoids.

Resistance:

37 –44Ω



(b) Connect the battery to the solenoid.

Check that air flow from the port E to port F.

Check that air does not flow from the port E to the air filter.



(c) Disconnect the battery positive voltage from the solenoid.

Check that air flows from the port E to the air filter.

Check that air does not flows from the port E to port F.



2. INSPECT A.D.D. RELAY

Continuity

Terminal / Condition	1	2	3	4	6
Constant	○	○	○		○
Apply battery positive voltage to terminals 5 and 2.	○			○	



3. INSPECT A.D.D. INDICATOR SWITCH

(a) Using an ohmmeter, check that there is continuing between terminals when the switch is pushed (differential connected position).

(b) Using an ohmmeter, check that there is no continuity when the switch is free (differential disconnected position).



4. Except 3VZ–E w/ATM:

INSPECT TRANSFER INDICATOR SWITCH

(a) Using an ohmmeter, check that there is continuity between terminals when the switch is pushed (transfer 4WD position).

(b) Using an ohmmeter, check that there is no continuity between terminals when the switch is free (transfer H 2 position).



5. 3vz – E w/ ATM:

INSPECT TRANSFER POSITION SWITCH

Using an ohmmeter–, check that there is continuity between each terminal.

Transfer position \ Terminal	1	2	3
H4	O		O
L4	O	O	O
H2			



6. 3VZ – E w/ ATM:

INSPECT TRANSFER PRESSURE SWITCH

While blowing compressed air (294 kPa, 43 psi, 3.0 kg/cm2) into the switch, using an ohmmeter, check the continuity between the terminal and switch body.

Resistance:

0Ω